

GENERAL NOTES

- CONSTRUCTION PLANS MUST BE ACCOMPANIED BY THE APPROVED SPECIFICATION. NO WORK IS TO COMMENCE WITHOUT EVIDENCE OF POSSSESION OF EACH.
- SHIRE OF MELTON AND TO THE SATISFACTION OF THE ENGINEER AND THE MUNICIPAL ENGINEER. IN CASE OF A DISPUTE THE SPECIFICATION MUST TAKE PRECEDENCE.
- COUNCIL TO BE NOTIFIED SEVEN (7) CLEAR DAYS PRIOR TO COMMENCEMENT OF WORKS.
- PROPERTY INLETS ARE TO BE PLACED 1.0m FROM THE LOW CORNER OF LOT UNLESS OTHERWISE SHOWN. MINIMUM COVER TO BE 500mm. REFER GAA STD DWGS EDCM701, EDCM702, EDCM703 & EDCM704.
- LOTS DENOTED THUS 'H' ARE TO BE PROVIDED WITH A 100mm DIA. HOUSE DRAIN PLACED 6.5m FROM LOW CORNER OF LOT UNLESS OTHERWISE SHOWN. REFER GAA STD DWGS EDCM701, EDCM702, EDCM703
- AGRICULTURAL PIPE DRAINS AS PER GAA STD DWG EDCM202 TO BE PLACED BEHIND ALL KERB AND CHANNEL AND BUFFER PITCHERS AND WHERE DIRECTED BY THE ENGINEER
- DRAINAGE AND PITS TO BE SET OUT FROM OFFSETS SHOWN RATHER THAN FROM PIPE CHAINAGES.
- DRAINAGE PIPES UPTO AND INCLUDING 750mm DIA TO BE CLASS 2 R.C. (RRJ). PIPES 825mm ANI GREATER TO BE CLASS 2 R.C. (IJ) UNLESS OTHERWISE SHOWN. ALL ROAD CROSSINGS AND PIPES LAID ON A CURVED ALIGNMENT TO BE RUBBER RING JOINTED.
- WHERE DRAINAGE PIPES ARE LOCATED WITHIN NATURE STRIPS. THE TRENCH SHALL BE BACKFILLED WITH COMPACTED CLASS 3 F.C.R. UP TO A LEVEL WHERE THE 45Deg. INFLUENCE LINE FROM THE B.O.K. INTERSECTS WITH THE NEAREST TRENCH SIDE. PROVIDE CRUSHED ROCK BACKFILL WHERE DRAINAGE CROSSES BELOW FOOTPATHS.
- PIPE TRENCHES WITHIN THE ROAD RESERVE MUST BE BACKFILLED WITH 20mm CLASS 3 CRUSHED
- PIPE I RENCHES WITHIN THE ROAD RESERVE MUST BE BACKFILLED WITH ZUMM CLASS 3 CROSHEU ROCK TO A RELATIVE COMPACTION OF 97% OF THE MAXIMUM FOUND IN THE STANDARD COMPACTION TEST FOR THE FOLLOWING:

 1) BENEATH THE ROAD OR DRIVEWAY PAVEMENT TO THE UNDERSIDE OF THE PAVEMENT.


 1) ADJACENT TO KERBING OR CONCRETE WORKS TO A LEVEL THAT IS NOT AFFECTED BY A 45 DEGREE ANGLE OF REPOSE FROM THE NEAR LOWER EDGE. (TRENCHES TO BE BACKFILLED IN LAYERS NOT EXCEEDING 200mm LOOSE).
- PRIOR TO COMMENCEMENT OF WORKS ON SITE, THE CONTRACTOR MUST ENSURE THAT ALL MATTERS RELATING TO THE OCCUPATIONAL HEALTH AND SAFETY ACT 2004, INCLUDING ALL RELEVANT REGULATIONS, HAVE BEEN ADDRESSED. IN PARTICULAR, THE REQUIRED NOTHICATIONS MUST BE CONVEYED TO THE VICTORIAN WORKCOVER AUTHORITY HEALTH & SAFETY DIVISION WITH RESPECT TO TRENCHING OPERATIONS, DETAILS OF THE CONTRACTORS OCCUPATIONAL HEALTH & SAFETY PROCEDURES MUST BE LODGED WITH THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF
- 12. BATTERS SHALL BE 1 IN 6 FOR FILL AND 1 IN 6 FOR CUT UNLESS OTHERWISE SHOWN.
- ON COMPLETION THE CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL OF ALL RUBBISH AND SPOIL
- LOTS TO BE GRADED AND LEFT CLEAN TO THE SATISFACTION OF THE ENGINEER, ALL LOTS TO BE 1 IN 150 MINIMUM SLOPE.
- ALL RESERVE AREAS ARE TO BE SMOOTHED GRADED TOP SOILED WHERE REQUIRED WITH A 100mm COMPACTED LAYER OF TOPSOIL AND SEEDED USING AN APPROVED SEED MIX AND METHOD OF SOWING, SUCH THAT THE SURFACE IS SELF-DRAINING, STONE FREE AND ABLE TO BE MAINTAINED BY
- FILL AREAS ARE TO BE STRIPPED OF TOPSOIL, FILLED AND TOPSOIL REPLACED TO OBTAIN FINAL FILL LEVELS AS SHOWN ON THE PLANS. FILLING TO BE CLEAN CLAY COMPACTED TO A DRY DENSITY NOT LESS THAN 95% OF THE MAXIMUM DRY DENSITY VALUE DETERMINED BY THE STANDARD COMPACTION TEST IN ACCORDANCE WITH AUSTRALIAN STANDARD AS1289.5.2.1-1993. TESTING TO COMPLY WITH AS3798-1996 APPENDIZ B, LEVEL 1.
- THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL IMPORTED FILL MATERIAL INCLUDING THE CONTRACTOR IS RESPONSIBLE FOR ENSORING THAT ALL IMPORTED FILE MATERIAL, INCLUDING TOPSOIL, SATISFIES THE DESCRIPTION FOR CLEAN FILL MATERIAL IN FEA BULLETIN PUBLICATION No. 448 (SEPT '95) AND SUBSEQUENT REVISIONS. THE CONTRACTOR SHALL PROVIDE VERIFICATION INCLUDING TEST CERTIFICATES TO THE SUPERVISING ENGINEER.
- EARTH FILL IS TO BE COMPACTED TO A RELATIVE COMPACTION COMPARED TO A STANDARD COMPACTION TEST AS SPECIFIED BY VICROADS CORPORATION OF: -100% FOR ALL FILL MATERIAL AND MATERIAL UNDER FILL THAT IS LESS THAN 450mm FROM 95% FOR ALL FILL NOT COVERED ABOVE.
- NATURE STRIP AND AREAS OF CUT ARE TO BE TOP SOILED AND GRASSED TO THE SATISFACTION OF
- ALL NATIVE TREES AND SHRUBS TO BE RETAINED UNLESS ROAD CONSTRUCTION NECESSITATES THEIR REMOVAL OR REMOVAL IS DIRECTED BY THE ENGINEER. NO EXCAVATION WITHIN 5m OF any existing native tree without approval of the engineer.
- 21. WHERE WORKS ARE IN THE VICINITY OF EXISTING SERVICES THESE SERVICES ARE TO BE LOCATED AND THE VARIOUS AUTHORITIES NOTIFIED, BY THE CONTRACTOR, PRIOR TO THE COMMENCEMENT OF
- SERVICE CONDUITS ARE TO BE PROVIDED AT 90deg TO KERB AND CHANNEL UNLESS OTHERWISE SHOWN AND THE LOCATION IS TO BE MARKED ON THE FACE OF KERB. ALL SERVICE CONDUITS TO BE MINIMUM STANDARD OF CLASS 6, WITH A MINIMUM COVER OF 75mm ABOVE TOP OF CONDUIT TO SUB GRADE LEVEL, AND A SIZE SUITABLE TO SERVICE BUT NOT LESS THAN 50mm.
- 23. WATER AND GAS CONDUITS TO BE CONSTRUCTED ACROSS NATURE STRIPS AFTER ELECTRICAL
- THE WATER CONDUIT OFFSET FROM THE LOT BOUNDARY IS GIVEN ON THE WATER RETICULATION PLAN. THE CONTRACTOR MUST CONSTRUCT CONDUITS TO ACCORD WITH THE GIVEN OFFSET AND ENSURE THAT THE CONCRETER MARKS THE KERB AND FOOTPATH EXACTLY ABOVE THE CONDUIT
- TELSTRA/NBN Co. TO BE NOTIFIED SEVEN (7) DAYS PRIOR TO CONCRETE WORKS BEING PLACED
- VEHICLE CROSSINGS TO BE OFFSET 0.75m FROM SIDE BOUNDARYS AND EASEMENTS UNLESS OTHERWISE SHOWN AND A MINIMUM OF 0.75m (LEAR OF PITS. VEHICULAR (ROSSINGS TO BE CONSTRUCTED IN ACCORDANCE WITH MELTON CITY COUNCIL STD DWGS MCC501 & MCC503.
- ALL RESIDENTIAL FOOTPATHS SHALL BE 1.5m WIDE (MIN.) AND SHARED PEDESTRIAN/CYCLE PATHS SHALL BE 3m (MIN.). CONCRETE PATHS ARE TO BE 125mm THICK REINFORCED WITH SL72 PLACED CENTRALLY AND UNDERLAIN BY 50mm OF CLASS 3 CR. REFER GAA STD DWG EDCM401.
- PRAM CROSSINGS ARE TO BE CONSTRUCTED WHERE FOOTPATHS CONNECT TO THE BACK OF KERB & CHANNEL. REFER MELTON CITY COUNCIL STD DWG MCC403.
- 29. STREET SIGNS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH COUNCIL STANDARDS.
- THE CONTRACTOR SHALL TO THE SATISFACTION OF THE ENGINEER AND THE MUNICIPAL ENGINEER PROVIDE AND MAINTAIN INCLUSIVE OF STREET SIGNS, ALL NECESSARY REGULATORY SIGNS, WARNING SIGNS, LIGHTING, LINE MARKING AND BARRICADING TO COMPLY WITH THE REQUIREMENTS OF VICROADS SIGNING CODE OF PRACTICE.
- THE CONTRACTOR IS TO SUPPLY AND ERECT ALL RELEVANT STREET SIGNAGE AND LINE MARKING AS PART OF THE CONTRACT IN ACCORDANCE WITH VICROADS SPECIFICATION SECTIONS 710 & 722 AND AS1742.1. 2 & 3.
- 32. ALL ROADS TO BE CONSTRUCTED WITH SM2 AND B2 KERB & CHANNEL. REFER GAA STD DWG EDCM301 &
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING A ROAD OPENING PERMIT FOR WORKS IN PREVIOUSLY CONSTRUCTED ROADWAYS.

- IF BLASTING IS REQUIRED THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING A PERMIT TO BLAST AND MAINTAINING SAFETY REGULATIONS ON SITE IN COMPLIANCE WITH THE EXPLOSIVES ACT 1960. THE PERSON WHO IS USING THE EXPLOSIVES ON THE SITE IS TO BE A HOLDER OF A CURRENT PERMIT TO USE EXPLOSIVES ISSUED UNDER THE EXPLOSIVES ACT 1960.
- 35. THE RELATIVE COMPACTION OF CRUSHED ROCK SHALL BE COMPLETED AT THE OPTIMUM MOISTURE CONTENT TO A DRY DENSITY (BASED ON THE PERCENTAGE OF THE MAXIMUM DRY DENSITY
 - OBTAINED IN THE MODIFIED COMPACTION TEST) AS BELOW.


 FOR DEPTH 0-100mm BELOW TOP OF BASE: RELATIVE COMPACTION = 100%

 FOR DEPTH 100-300mm BELOW TOP OF BASE: RELATIVE COMPACTION = 98%


 FOR DEPTH 004-300mm BELOW TOP OF BASE; RELATIVE COMPACTION = 97%
- THE SUBGRADE BELOW ALL PAVEMENTS SHALL BE COMPACTED TO A DRY DENSITY OF NOT LESS THAN 100% OF THE MAXIMUM DRY DENSITY OBTAINED IN THE STANDARD COMPACTION TEST IN AREAS OF CUT TO A DEPTH OF 150mm AND IN AREAS OF FILL TO A DEPTH OF 450mm.
- 37. CONCRETE TO HAVE A 28 DAY STRENGTH OF 25 Mpg.
- 38. ALL SPLAYS ARE 3.00m X 3.00m UNLESS OTHERWISE SHOWN.
- 39. ALL LEVELS ARE TO THE AUSTRALIAN HEIGHT DATUM (A.H.D.)
- 40. EXISTING DAM OR WATERCOURSES TO BE EXCAVATED TO A FIRM BASE AND BACKFILLED AS SPECIFIED. DEVELOPER'S CONSULTANT TO BE NOTIFIED WHEN THE DAM OR WATERCOURSES ARE EXCAVATED TO A FIRM BASE. NO FILLING IS TO BE PLACED PRIOR TO DAMS BEING INSPECTED AND LEVELS TAKEN. BACKFILING IS TO BE CARRIED OUT TO THE SATISFACTION OF THE COUNCIL
- THE CONTRACTOR MUST COMPLETE A LEVEL CHECK BETWEEN ALL TBM'S TO VERIFY LEVEL VALUES BEFORE COMMENCEMENT OF WORKS. ALL TBM'S AND CONTROL POINTS ARE TO BE MAINTAINED AND PROTECTED AT ALL TIMES DURING CONSTRUCTION. SHOULD ANY MARKS BE DISTURBED, THE CONTRACTOR WILL IMMEDIATELY NOTIFY THE DEVELOPER'S CONSULTANT TO ARRANGE RE-INSTALLATION AT THE CONTRACTORS EXPENSE.
- 42. PRIOR TO COMMENCEMENT OF WORKS. THE CONTRACTOR MUST SUBMIT A SMP TO THE DEVELOPER'S CONSULTANT FOR APPROVAL. THE CONTRACTOR MUST COMPLY WITH THE RECOMMENDATIONS OF THE ENVIRONMENT PROTECTION AUTHORITY PUBLICATION No.275 "CONSTRUCTION TECHNIQUES FOR SEDIMENT POLLUTION CONTROL", APPROPRIATE SILTATION CONTROL IS TO BE MAINTAINED THROUGHOUT THE CONSTRUCTION AND MAINTENANCE PERIOD OF THE WORKS.
- PROVIDE 1.8m HIGH PALING FENCE ALONG ANY COMMON BOUNDARY BETWEEN A LOT AND MUNICIPAL RESERVE. PALINGS TO BE ON THE RESERVE SIDE AND STAINED IN A DARK GREEN COLOUR ON THE SIDE FACING THE RESERVE TO THE SATISFACTION OF COUNCIL.









TYPICAL SECTION A - A 16.0m ROAD RESERVE COOK ROAD, ANTONIO DRIVE & FREESTONE AVENUE





PAVEMENT COMPOSITION - ALL ROADS


TOTAL PAVEMENT DEPTH 520mm











| | | | | | | | י ענ | 9 (| 5) | |
|-----------------------------|---------|---|------|---------|---------|---------|----------|---------|------|---------|
| VC LENGTH | | | | | | | , | | | |
| KERB GRADING DATUM IP112 | | < | 0.5% | > | 0.5%_ | -0.8 | 39% > | 0.5%_ | 0.5% | _> |
| LIP OF KERB | 112.604 | | | 112.629 | 112.613 | 112.582 | 112.552 | 112.535 | | 112.560 |
| LIP CHAINAGE | -5.000 | | | 0.000 | 3.377 | 6.754 | 10.132 | 13.509 | | 18.509 |

| KERI | B SETOUT | POINTS - | LIP D |
|-------|-----------|-----------|----------|
| POINT | FASTING | NORTHING | LIPLEVEL |
| 1 | 1646.9940 | 1974.1880 | 112.629 |
| 2 | 1647.2450 | 1970.8420 | 112.613 |
| 3 | 1648.7580 | 1967.8470 | 112.582 |
| 4 | 1651.3020 | 1965.6590 | 112.552 |
| 5 | 1654.4900 | 1964.6110 | 112.535 |

LIP LINE D

POINT EASTING NORTHING LIPLEVEL 1653,7160 1650.3690 1958.0060 112.571 1647.3740 1956.4930 112.644 1645.1860 1953.9490 112.717 1644.1380 1950.7610 112.752


1:20 VER 0.4 0.2 00


1:200 HOR 4 2 00


KERB SETOUT POINTS - LIP C

ALL SETOUT DETAILS ARE PROVIDED AT LIP OF KERB

WARNING
BEWARE OF UNDERGROUND SERVICES
THE LOCATIONS OF UNDERGROUND SERVICES ARE
APPROXIMATE ONLY AND THEIR EXACT POSITION
SHOULD BE PROVEN ON SITE. NO GUARANTEE IS
GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.









LIP LINE E


| KERB SETOUT POINTS - LIP E | | | | | | | | | | | |
|----------------------------|-----------|-----------|-----------|--|--|--|--|--|--|--|--|
| POINT | EASTING | NORTHING | LIP LEVEL | | | | | | | | |
| 1 | 1662.9120 | 2033.7000 | 112.794 | | | | | | | | |
| 2 | 1659.5650 | 2033.4480 | 112.811 | | | | | | | | |
| 3 | 1656.5700 | 2031.9350 | 112.838 | | | | | | | | |
| 4 | 1654.3820 | 2029.3910 | 112.865 | | | | | | | | |
| 5 | 1653.3340 | 2026.2030 | 112.882 | | | | | | | | |


| _ | | | | |
|---|-------|-----------|-----------|-----------|
| | KERI | B SETOUT | POINTS - | LIP F |
| r | POINT | EASTING | NORTHING | LIP LEVEL |
| Γ | 1 | 1656.1900 | 2049.6300 | 113.002 |
| r | 2 | 1656.4410 | 2046.2840 | 112.967 |
| t | 3 | 1657.9540 | 2043.2890 | 112.898 |
| r | 4 | 1660.4980 | 2041.1010 | 112.828 |
| r | 5 | 1663.6860 | 2040.0530 | 112.794 |


| | | | | P | | reese pi d surveyors | | pty. Itd. engineers | 1/19 cato stree hawthorn east, 3 telephone 8823 2 fax no. 8823 2 | 123 2300 |
|------------|------|----------|-------------------------|-------------|--------|-------------------------|-----------|------------------------|---|-------------|
| AMENDMENTS | | | | MELWAY REF. | 342 J5 | UDCHVD | D GREEN | FSTATE | MUNICIPALITY | |
| MEND | | | | SURVEY | BPD | | STAGE 4E | | MELTON | |
| 1 | | | | DESIGN | JGB | | | | REFERENCE | |
| 1 | Α | 21.04.20 | ISSUED FOR CONSTRUCTION | DRAWN | IMW | INTERSECTION DETAILS | | | 7776 - E/4 | В |
| Т | VER. | DATE | REMARKS | CHECKED | - | SCALE AS SHOWN | DATUM AHD | DATE FEB '20 | SHEET 4 OF 12 | Α |
















| | | | | | | reese pi d surveyors | | pty. Itd. engineers | 1/19 cato stree hawthorn east, 3 telephone 8823 2 fax no. 8823 2 | 3123 2300 |
|--------------|-------|----------|-------------------------|-------------|-----|-------------------------|------------|------------------------|---|--------------|
| AMENIOMENITE | DWCIN | | | MELWAY REF. | | ORCHAR | D GREEN | ESTATE | MUNICIPALITY MELTON | |
| ĺ | | | | SURVEY | BPD | | CT |) | TILLTON | |
| ľ | Ĺ | | | DESIGN | JGB | | STAGE 4E | | REFERENCE | |
| ı | Α | 21.04.20 | ISSUED FOR CONSTRUCTION | DRAWN | IMW | COOK | ROAD - SHI | EET 2 | 7776 - E/4 | ·B |
| L | VER. | DATE | REMARKS | CHECKED | - | SCALE AS SHOWN | DATUM AHD | DATE FEB '20 | SHEET 6 OF 12 | Α |




VERTICAL SCALE - 1:50 HORIZONTAL SCALE - 1:500





| | | | | | | reese pi | | pty. Itd. engineers | 1/19 cato str hawthorn east, telephone 8823 fax no. 8823 | 3123 2300 |
|------------|------|----------|-------------------------|-------------|--------|----------------|------------|--------------------------|---|--------------|
| AMENDMENTS | | | | MELWAY REF. | 342 H5 | NRCHAR | D GREEN | FSTATE | MUNICIPALITY MF1 TON | |
| MFN | | | | SURVEY | BPD | | | | MELTON | |
| | 11 | | | DESIGN | JGB |] | STAGE 4E | 3 | REFERENCE | |
| - | Α | 21.04.20 | ISSUED FOR CONSTRUCTION | DRAWN | IMW | FRE | ESTONE AVE | NUE | 7776 - E/ | 4B |
| | VER. | DATE | REMARKS | CHECKED | - | SCALE AS SHOWN | DATUM AHD | DATE FEB '20 | SHEET 7 OF 12 | A |



INTERSECTION WITH COOK ROAD

1/19 cato street hawthorn east, 3123

telephone 8823 2300 fax no. 8823 2310


7776 - E/4B

SHEET 8 OF 12 A

UNICIPALITY

EFERENCE

MELTON



LEGEND:

---EXISTING SURFACE PROFILE

——FINISHED SURFACE PROFILE


INDICATES CRUSHED ROCK BACKFILL

HGL—HYDRAULIC GRADE LINE

ALL PIPES TO BE CLASS 2 UNLESS SHOWN OTHERWISE RRJ DENOTES RUBBER RING JOINTED FJ DENOTES FLUSH JOINTED WITH EXTERNAL SEALING BANDS



| | | | | | | reese pi | | pty. Itd. engineers | 1/19 cate hawthorn telephone fax no. | east, 31 8823 2 | 123 300 |
|------------|------|----------|-------------------------|-------------|-------------------------------|----------------|-----------|------------------------|---|--------------------|------------|
| AMENDMENTS | | | | MELWAY REF. | 342 J5 | UDCHVD | D GRFFN | FSTATE | MUNICIPALITY | | |
| NE NO | | | | SURVEY | BPD | 1 0 | 0 | | MELTON | N | |
| | | | | DESIGN | JGB |] : | STAGE 4E | 3 | REFERENCE | | |
| Т | Α | 21.04.20 | ISSUED FOR CONSTRUCTION | DRAWN | RAWN IMW DRAINAGE LONGITUDINA | | | SECTIONS - 1 | 7776 - | E/4 | В |
| 1 | VER. | DATE | REMARKS | CHECKED | - | SCALE AS SHOWN | DATUM AHD | DATE FEB '20 | SHEET 09 OF | 12 | Α |



---EXISTING SURFACE PROFILE

----FINISHED SURFACE PROFILE

HGL—HYDRAULIC GRADE LINE

ALL PIPES TO BE CLASS 2 UNLESS SHOWN OTHERWISE RRJ DENOTES RUBBER RING JOINTED FJ DENOTES FLUSH JOINTED WITH EXTERNAL SEALING BANDS




| | | | | | | preese pi | | pty. Itd. engineers | 1/19 cat hawthorn telephone fax no. | 8823 2 | 123 300 |
|--------------|------|----------|-------------------------|-------------|--------|----------------------------------|-----------|------------------------|--|--------|------------|
| AMENIDMENITO | | | | MELWAY REF. | 342 J5 | ПРСНАР | D GRFFN | FSTATE | MUNICIPALITY | | |
| Ş | | | | SURVEY | BPD | 0110111111 | 0 | | MELTON | N | |
| ľ | П | | | DESIGN | JGB |] : | STAGE 4E | 3 | REFERENCE | | |
| ı | Α | 21.04.20 | ISSUED FOR CONSTRUCTION | DRAWN | IMW | DRAINAGE LONGITUDINAL SECTIONS - | | | 7776 - | E/4 | В |
| П | VER. | DATE | REMARKS | CHECKED | - | SCALE AS SHOWN | DATUM AHD | DATE FEB '20 | SHEET 10 OF | 12 | Α |



INDICATES CRUSHED ROCK BACKFILL

PIT SCHEDULE

| PIT | PIT DESCRIPTION | WIDTH | LENGTH | INL | ET | OUT | LET | TOP | DEPTH | REMARKS |
|-----|--------------------------------|-------|--------|-----|---------|-----|---------|---------|--------|--|
| No. | | | [| DIA | INVERT | DIA | INVERT | PIT RL | INVERT |] |
| 20A | EXISTING END CAP | | | | | 300 | 110.784 | 112.912 | 2.128 | Connect to Existing Drainage Pipe |
| 21A | EXISTING END CAP | | | | | 450 | 110.476 | 112.912 | 2.436 | Connect to Existing Drainage Pipe |
| 22 | SIDE ENTRY PIT - GRATED | 600 | 900 | 375 | 110.663 | 450 | 110.653 | 112.89 | 2.237 | Refer Standard Drawing - EDCM 601 |
| 23 | SIDE ENTRY PIT - GRATED | 600 | 900 | 375 | 110.822 | 375 | 110.812 | 112.764 | 1.952 | Refer Standard Drawing - EDCM 601 |
| 24 | SIDE ENTRY PIT - GRATED | 600 | 900 | 375 | 111.105 | 375 | 111.095 | 113.014 | 1.919 | Refer Standard Drawing - EDCM 601 |
| 25 | SIDE ENTRY PIT - GRATED | 600 | 900 | 300 | 111.238 | 375 | 111.163 | 112.925 | 1.763 | Refer Standard Drawing - EDCM 601 |
| | | | | 225 | 111.475 | | | | | |
| 26 | SIDE ENTRY PIT - GRATED | 600 | 900 | | | 300 | 111.328 | 112.925 | 1.597 | Refer Standard Drawing - EDCM 601 |
| 27 | JUNCTION PIT | 600 | 900 | | | 225 | 111.97 | 113.413 | 1.443 | Refer Standard Drawing - EDCM 605 |
| 140 | SIDE ENTRY PIT - GRATED | 600 | 900 | 300 | 111.255 | 300 | 111.245 | 112.777 | 1.532 | Refer Standard Drawing - EDCM 601 |
| 141 | SIDE ENTRY PIT - GRATED | 600 | 900 | 300 | 111.681 | 300 | 111.671 | 113.15 | 1.479 | Refer Standard Drawing - EDCM 601 |
| 142 | SIDE ENTRY PIT - GRATED | 600 | 900 | | | 300 | 111.766 | 113.137 | 1.371 | Refer Standard Drawing - EDCM 601 |
| 147 | DOUBLE SIDE ENTRY PIT - GRATED | 600 | 900 | 225 | 111.281 | 300 | 111.005 | 112.681 | 1.676 | Refer Standard Drawing - EDCM 602 |
| | | | | 300 | 111.19 | | | | | |
| 148 | JUNCTION PIT | 600 | 900 | | | 225 | 112.095 | 113.495 | 1.4 | Refer Standard Drawing - EDCM 605 |
| 149 | DOUBLE SIDE ENTRY PIT - GRATED | 600 | 900 | 225 | 111.266 | 300 | 111.236 | 112.666 | 1.43 | Refer Standard Drawing - EDCM 602 |
| 150 | JUNCTION PIT | 600 | 900 | | | 225 | 111.12 | 113.52 | 1.4 | Refer Standard Drawing - EDCM 605 |
| 151 | JUNCTION PIT | 600 | 900 | | | 225 | 111.933 | 113.383 | 1.45 | Refer Standard Drawing - EDCM 605 |
| 300 | JUNCTION PIT | 600 | 900 | 225 | 112.29 | | | 113.259 | 0.969 | Convert Existing Cover to Heavy Duty Class D Trafficable Cover |
| | | | | | | | | | | E 1654.0793 N 2079.7611 |
| 301 | JUNCTION PIT | 600 | 900 | | | 225 | 112.309 | 113.282 | 0.973 | Refer Standard Drawing - EDCM 605 |
| | | | | | | | | | | E 1652.4372 N 2077.9245 - E 1652.3278 N 2077.0478 |
| 305 | SIDE ENTRY PIT - GRATED | 600 | 900 | 225 | 112.290 | | | 113.316 | 1.026 | Adjust Cover to Suit New Levels. Refer Standard Drawing - EDCM 601 |
| 306 | JUNCTION PIT | 600 | 900 | 225 | 112.315 | 225 | 112.305 | 113.269 | 0.963 | Refer Standard Drawing - EDCM 605 |
| | | | | | | | | | | E 1660.2812 N 2076.9853 - E 1660.1710 N 2076.0920 |
| 307 | GRATED - JUNCTION PIT | 600 | 900 | 225 | 112.445 | 225 | 112.435 | 113.290 | 0.855 | Refer Standard Drawing - EDCM 605 |
| | | | | | | | | | | E 1678.7681 N 2074.5810 - E 1679.6612 N 2074.4695 |
| | | | | | | | | | | Replace Cover with Heavy Duty Type D - Gatic Lid |
| 308 | GRATED - JUNCTION PIT | G00 | 900 | | | 225 | 112.728 | 113.498 | 0.770 | Refer Standard Drawing - EDCM 605 |
| | | | | | | | | | | E 1722.9410 N 2069.1971 - E 1723.8341 N 2069.0859 |
| | | | | | | | | | | Replace Cover with Heavy Duty Type D - Gatic Lid |



LEGEND:

---EXISTING SURFACE PROFILE

——FINISHED SURFACE PROFILE

HGL—HYDRAULIC GRADE LINE

ALL PIPES TO BE CLASS 2 UNLESS SHOWN OTHERWISE RRJ DENOTES RUBBER RING JOINTED FJ DENOTES FLUSH JOINTED WITH EXTERNAL SEALING BANDS



| _ | | | | | | | | | | | |
|--------------|-----|----------|-------------------------|-----------------------|---------------|-------------------------|--------------------------|------------------------|--|--------------------|-------------|
| | | | | | | reese pi d surveyors | | pty. Itd. engineers | 1/19 cat hawthorn telephone fax no. | east, 3° 8823 2 | 123 2300 |
| AMENIDMENITE | | | | MELWAY REF. SURVEY | 342 J5 BPD | • | D GREEN | | MUNICIPALITY MELTON | ١ | |
| ľ | L | 21.04.20 | ISSUED FOR CONSTRUCTION | DESIGN DRAWN | JGB IMW | | STAGE 4E IAGE PIT SCH | - | REFERENCE 7776 - | E/4 | В |
| | VER | DATE | REMARKS | CHECKED | - | SCALE AS SHOWN | DATUM AHD | DATE FEB '20 | SHEET 11 OF | 12 | Α |



SIGNAGE LEGEND

A STREET SIGNS (Q5-1) NOTES

a) ALL SIGNS TO BE SLEEVED USING A SL27 SLEEVE.

b) ⊡€ ≥⊡€ INDICATES UNIDIRECTIONAL & BIDIRECTIONAL RRPM'S PLACED AT 6.00m CTS

c) HAZARD / DIRECTIONAL TGS/S SHOWN THUS [] / AND FOOTPATH RAMPS SHALL BE CONSTRUCTED IN ACCORDANCE WITH VICROADS STD DWGS 502031 TO 502035. TGS/S SHALL CONFORM TO A53428.4

d) STREET SIGNS TO HAVE MINIMUM 2 WEDGES IN THE SLEEVES

e) SWLM - INDICATES SOLID WHITE "LONGLIFE" LINE MARKING BWLM - INDICATES BROKEN WHITE "LONGLIFE" LINE MARKING

SYMBOL LEGEND

Drains
Sewer <300
Sewer >300

breese pitt dixon pty. Itd.

land surveyors civil engineers

SURVEY

DESIGN

DRAWN

CHECKED

A 21.04.20 ISSUED FOR CONSTRUCTION

BPD

JGB

IMW

1/19 cato street
hawthorn east, 3123
telephone 8823 2300
fax no. 8823 2310

ORCHARD GREEN ESTATE

STAGE 4B

SIGNAGE AND LINEMARKING PLAN

SCALE AS SHOWN DATUM AHD

OATOM AHD

MUNICIPALITY
MELTON

REFERENCE

7776 - E/4B

SCALE AS SHOWN DATUM AHD

DATE FEB '20

SHEET 12 0F 12

A

1:500 10 5 00 10 20 40